

## 2021 TRADE SCOPES INDEX

### ACOUSTIC TILE & SUSPENSION SYSTEMS SCOPE

Page 1 of 2  
Revised 2003

This contractor shall include the following items regardless of where they may appear in the tender documents unless specifically noted otherwise in this Scope.

#### INCLUDED:

1. Acoustical
  - a) Tile
  - b) Lay-in panels for use in T-Bar
  - c) Batts – over ceiling high partitions for sound attenuation purposes (laid on ceiling).
2. Acoustical adhesives, staples, nails and screws for acoustical tile.
3. Premanufactured individual acoustically rated units applied to surfaces prepared by others (e.g. Tectum, Soundsoak, Sonotrol and Geocoustic).
4. Fire protection to recessed fixtures in time-rated acoustical ceilings as required to meet any specified time rating.
5. Inserts and hangers – capable of supporting acoustic ceiling and all light fixtures supported by ceiling. Supports for mechanical equipment and folding doors by others.
6. Perforated lay-in panels where used with acoustic absorption behind.
7. Sound attenuation baffles, i.e. lead shield (except those made of lath and plaster, drywall and steel studs or rigid insulation).
8. Luminous and translucent ceilings including suspension system, reflective foil and backing if specified, (i.e. leaf-type reflectors, eggcrate and translucent panels).
9. **SYSTEMS:**
  - a) Exposed grid – standard and fire-rated
  - b) Perforated metal pan and suspension
  - c) Concealed or semi-concealed
  - d) Integrated ceiling systems, **NOTE:** The supply and installation of all fixtures, ballasts, lamps and lenses for use in an integrated ceiling will remain under the electrical scope (see Electrical Scope Included Item 45).  
**NOTE:** Supply and installation of mechanical boots and deflectors for use in an “integrated” ceiling will be by the Acoustics Trade.
  - e) Linear metal ceilings complete with acoustic overlays where applicable.
10. Vinyl covered gypsum panels when used in suspended T-Bar ceilings.
11. Gypsum drywall panels where used in suspended T-Bar ceilings. (Painting of panels by others.)
12. Guarantee – One-year labour and materials from date of completion unless otherwise shown in specification.
13. Scaffolding for acoustical work.
14. Clean up for acoustic work.
15. Patching of existing acoustic tile and suspension system included where specifically shown on architectural drawings
16. Any steel stud framing or furring exclusively required for the installation of “Metal Linear” type ceilings.
17. Hoisting for materials and equipment.
18. Removal of existing acoustic tile and suspension system where the existing ceiling materials are being re-used in the new construction.

## 2021 TRADE SCOPES INDEX

### ACOUSTIC TILE & SUSPENSION SYSTEMS SCOPE

Page 2 of 2

**EXCLUDED:**

Temporary heat, light, power (up to a maximum of 120/280 volts and an adequate amperage for temporary lighting, heating and convenience outlets, sanitation) or as specified.

1. Acoustical plaster.
2. Caulking.
3. Gypsum backing for acoustical work.
4. Gypsum board and furring system when gypsum board is taped and filled for painting.
5. Sprayed acoustical materials.
6. Wood grounds.
7. Temporary heat, light, power and sanitation.
8. Hoarding.
9. Water.
10. Return air diffusers of any type.
11. Supply and installation of acoustic rated units where they are an integral part of demountable partition. (This will be included in Demountable Partitioning Scope – e.g. Soundsoak, Sonotrol and Tectum.)
12. Final cleaning.
13. Any drywall work above ceilings (e.g. for attenuation purposes).
14. Light fixture diffusers.
15. Thermal insulation of any kind.
16. Supply and installation of Acoustic Ceiling Grid when used as trim for radiant panels and/or lights in drywall assemblies.
17. Additional wires, chains, hangers and/or inserts required for support of radiant panels or electrical fixtures.